Franklin County School District

Chris Kent, Superintendent Post Office Box 605 Meadville, MS 39653 Phone: 601-384-2340 Fax: 601-384-2393

June 3, 2021

Bid Specifications

This project will be funded under provisions of the Coronavirus Response and Relief Supplemental Appropriations Act (CRRSAA). Certain mandatory federal requirements apply to this solicitation and will be made a part of any contract awarded, including but not limited to: (a) Davis Bacon Act (DOL Regulation 29 CFR Part 5), (b) Suspension and Debarment (Executive order 12549 and 12689, 2 CFR part 180), (c) Contracting with small and minority business enterprise and labor surplus area firms, 2 CFR §200.321, (d) Domestic Preferences for Procurements, 2 CFR §200.322, (e) affirmative action to ensure Equal Employment Opportunity (Executive order 11246 as amended by Executive order 11375 and DOL Regulation 41 CFR Part 60).

Location: Franklin County High School (Section 1)

Scope of Work (includes all materials and labor)

- Remove two (2) sets of 7'x10' exterior doors and frames
- Add wood stud framing to each of the voided areas
- Add 7/16" exterior wall sheeting
- Add R-13 fiberglass batt wall insulation
- Supply and install estimated ½" bc plywood for interior wall finish with 1x4 trim
- Supply and install estimated 1,080 modular face brick with all necessary mortar and sand
- Apply water proofer to face of masonry units
- Cut, break, and partially remove 120 square feet of existing concrete steps and retaining walls
- Remove all demolished concrete to off-site location
- Cut, break, and demolish 3'x10' concrete canopy (structural steel modifications as needed to remove)
- Masonry repair as needed for original canopy area
- Backfill and compact original stairwell as needed
- Add topsoil to create a slope against the brick wall to help direct surface water away from building
- Add sod to prevent erosion to selected areas of construction
- Paint immediately affected interior wall sheeting and new trim

Franklin County School District

Chris Kent, Superintendent Post Office Box 605 Meadville, MS 39653 Phone: 601-384-2340

Fax: 601-384-2393

- Pour an estimated 6'x22'x4" concrete sidewalk cap over the retaining walls for the construction area located outside the south side of the building
- Dispose all construction debris

Section 2

- Remove one (1) set of 7'x10' exterior doors and frames
- Remove exterior wall sheeting and framing
- Add 2x4 framing to support an elevated 42" wide x 7' tall hollow-metal jamb door with ½ glass
- Add 7/16" exterior wall sheeting
- Add R-13 fiberglass batt wall insulation
- Supply and install estimated ½" bc plywood for interior wall finish with 1x4 trim
- Additional interior modifications include removing and replacing one (1) interior door with inswing capabilities
- Supply and install 42" exterior door with hardware
- Form and pour an estimated 5'x14' ADA grade ramp w/landing for exterior of building
- Fabricate and install ADA compliant 1-1/4" schedule 40 pipe rail for outer edge of ramp and landing
- Supply and install masonry material and labor for an estimated 9'x10' area of exterior wall
- Construct a 10' interior concrete ramp with natural grey finish
- Add topsoil to create a slope against the brick wall to help direct surface water away from building
- Add sod to prevent erosion to selected areas of construction
- Paint immediately affected interior wall sheeting and new trim
- Dispose all construction debris

Total Price			

Franklin County School District

Chris Kent, Superintendent Post Office Box 605 Meadville, MS 39653 Phone: 601-384-2340

Fax: 601-384-2393

NOTE: The above specifications shall be as specified or an approved equal. The above bid prices for the Franklin County High School classrooms shall include shipping/handling of all materials to Franklin County High School, 340 Edison, Meadville, MS 39653.

NAME OF COMPANY _		
ADDRESS		
SIGNATURE OF COMP	ANY REPRESENTATIVE	
DATE	_ TELEPHONE #	FAX #
PRICES ARE GOOD FO	R DAYS.	