



Murray County Schools

P.O. Box 40 / 1006 Green Rd.

Chatsworth, GA 30705

Phone: 706-695-4531 / Fax: 706-695-8425

“Committed to Student Success! No Exceptions, No Excuses!”

Request for Quotation

MCBOE Facilities Department

Murray County Schools Facilities Department is requesting bids from qualified contractors for Gladden Middle School . The scope of work includes demolition and modification of concrete and masonry in the front of the building .

All questions concerning this project will be sent via email to chris.crow@murray.k12.ga.us

A site survey is mandatory to bid on the project , however no mandatory bid meeting date will be set . Contractors interested in bidding shall set up a site visit prior to June 7th. All bids shall be delivered to Murray County Schools Central Office , located at 1006 Green Road , Chatsworth Ga , 30705. Bid will be due on or before June 22nd @ 10:00 am .Bids received after the specified time will be rejected .

Demolition :

Remove and haul to offsite location :

Existing handicapped ramp (Concrete and Northside brick wall)

Existing concrete stairs / handrails (East & West entrances)

All existing wood top benches

Entire awning from building to lower parking lot

Lower concrete area (from mailbox 253' East and from building to asphalt)

Footings :

Footings supporting ramp retaining walls will be 36" x 12" reinforced with three (3) #5 rebar continuous.

Footings supporting bench retaining walls will be 24" x 12" reinforced with two (2) #5 rebar continuous .

All concrete used in footings will be 3,000 P.S.I.

Concrete Walls :

63' of 8" sloped concrete ramp walls reinforced with #5 rebar @ 12" o/c horizontally and 18" o/c vertically.

Plain Concrete Pads :

1- 223 sq.ft.x 6" deep ramp (flush with brick rowlock)

1- 78 sq.ft. x 6" deep upper bench (flush with top of existing brick wall)

1- 78 sq.ft. x 6" deep lower bench pad (flush with top of new brick wall)

Pads will be 3,000 psi concrete , reinforced with 6x6x10/10 wire mesh . Pads will receive one coat of sealer & hardener. All concrete will be standard grey color .

Stamped Concrete Pads :

1- 827 sq.ft. x 6" deep East upper entrance pad

1- 756 sq.ft. x 6" deep West upper entrance pad

1- 5650 sq.ft. x 6" deep lower entrance pad (slope concrete from building to 1-1/2" higher than asphalt)

Pads will be 3,000 psi concrete , poured on grade , reinforced with 6x6x10/10 wire mesh . Pads will receive one coat of sealer & hardener. All concrete will be standard gray color .

Concrete Stairs :

Form and pour concrete stairs. Stairs shall have 14" treads with one #5 rebar each and five risers of equal height . Stairs will receive one coat of sealer & hardener.

Masonry :

Furnish and install 60' of 8" block bench with brick veneer to match existing brick (one side with brick rowlock)

Furnish and install brick veneer ramp retaining walls (one side with brick rowlock)

Areas to be filled , i.e. ramp, stairs, benches ect. will be filled with #57 stone and/or compacted graded aggregate base .

Accessories:

12- Furnish and install mill finish aluminum handrails at stairs.

2-Furnish and install mill finish aluminum handrails at handicapped ramp. Handrails to be sleeved and grouted in place.

Notes:

All quantities and measurements must be verified by the contractor.

Landscaping by Owner.

Bond shall be included in the proposal .

