

Notice to Bid

The Wayne County Board of Education is accepting bids for Stadium Concrete Renovations as follows:

Collinwood High School (CHS) Football Stadium Concrete Renovations

Bids must be submitted in a sealed envelope labeled "CHS Football Stadium Concrete Renovation Bids" by 2:00 P.M, Friday, 13 May 2022.

The project will include the preparation of current structures as necessary, furnishing all materials and support such as necessary excavation, concrete, rebar, forming materials, surface grout to complete the following concrete repair/replacement.

All work will be completed by 1 August 2022.

NOTE: All measurements are close approximations and may not reflect the actual materials necessary to complete the project. It is for this reason that there will be two on-site pre-bid meetings at the stadium to review the project scope and allow bidders to make their own measurements and assessments of the project prior to bidding. The dates and times of these meetings are: 3 May 2022, 08:30 A.M. and 6 May 2022, 08:30 A.M.

Work Description:

L = Length, W = Width, T = Thickness, D = Depth front to back

Retaining/Knee Walls

Concession stand area retaining wall:

L = 85' H = 3' T = .5' Approximately 4.75 cubic yards

Home Side (Right) Retaining/Knee wall:

L = 139' H = 2.25' average (tapers from 27" to 19") T = .5' Approximately 5.8 cubic yards

Home Side (Left) Retaining/Knee wall:

L = 69' H = 3.5' T = .5' Approximately 4.5 cubic yards

Trojan Blvd. (East End) retaining/Knee wall:

L = 60' H = 1.75' T = .5' Approximately 2 cubic yards

Visitors Side Retaining/Knee Wall

L = 237' H = 2.25' average (Tapers from 33" to 19") T = .5' Approximately 10 cubic yards

Total area of sidewalks to be poured and finished for foot traffic:

W = 10' L = 575' T = .33' Approximately 70 cubic yards

W = 8' L = 190' T = .33' Approximately 19 cubic yards

Grouting of surfaces to restore finish and protect from further weathering:

Home Side Grouting:

108 Steps W = 4' D = 1.4' Approximately 604 Sq. Ft. of area

38 seat platforms W = 55' D = 2.66' Approximate 5,573 Sq. Ft.

1 seat platform W = 19' D = 2.66' Approximate 50.5 Sq. Ft.

Top of bleacher area Approximately 1,102 Sq. Ft

Visitor Side Grouting:

93 steps W = 4' D = 1.5' Approximately 558 Sq. Ft.

30 seat platforms W = 55' D = 3' Approximately 4,950 Sq. Ft.

Top of Bleacher area Approximately 732 Sq. Ft.

Stairs on east end to Trojan Blvd.

Approximately 424 Sq. Ft.

Total surface area to be grouted is Approximately 13,994 Sq. Ft.

BID AMOUNT:

Concrete work (Retaining Walls and Sidewalks)

Amount Bid: _____

Grouting Surface Areas Not Replaced

Amount Bid: _____