

ELMORE COUNTY BOARD OF EDUCATION BID NO. 24-005 NETWORK SWITCHES AND NETWORK CABLING & SUPPORT SERVICES

DATE: February 27, 2024, ADDENDUM #4

Notice to contractors. You are hereby notified of the following changes in the plans and specifications, which shall take precedence over anything published prior to this date.

Sealed proposals will be received by Elmore County Board of Education, 809 Micanopy Street, Wetumpka, AL 36092, until Friday, March 8, 2024 @ 10:00 AM CST, when they will be publicly opened and reviewed. Decisions will not be made at this meeting. You must have attended one of the 2 walk-throughs to participate in this bid as stated in the original RFP 24-005.

Fiber Runs and IDF Cabinets

WHS

- Underground fiber run from main building to Agriculture Shop
- Underground to new gym in existing pipe
- Replace cabinet in Ag shop with a 10U lockable cabinet
- Add at least a 15U lockable cabinet for D Wing
- Add a 10U lockable cabinet in Rm G3
- 200 crimp end drops
- 300 punch down drops

SEHS

- Underground fiber ran between 100 building and 300 building
- Underground fiber ran between 100 building and 200 building
- Underground fiber ran between 600 building and main in existing pipe
- Fiber ran to 700 building follow current fiber run
- Add at least a 15U lockable cabinet in Rm 303
- Add at least a 15U lockable cabinet in Rm 204
- Add at least a 15U lockable cabinet in 600 building where IDF is currently located
- Add at least a 15U lockable cabinet in Rm 112 (IDF currently across the hall in rm 109 – moving IDF to Rm 112)
- Add a 10U lockable cabinet to the new gym office
- 245 crimp end drops
- 305 punch down drops

HHS

- Underground fiber ran between main building and Science Lab building
- Underground fiber ran from main building to classrooms 9-13 building
- Fiber run from main building to new gym underground in existing pipe
- Overhead fiber ran from main building to Ag Shop

- Overhead fiber ran between main building and classrooms 14-19 building
- Overhead fiber ran from main building to fitness center/rms 118-122 building
- Add a 10U lockable cabinet in library storage room IDF
- Add 10U lockable cabinet in Room 17 (New IDF)
- Add lockable 10U lockable cabinet in Room 13 (New IDF)
- Replace cabinet in Ag shop with a 10U lockable cabinet
- Move IDF from Rm 113 to Office hallway across the hall and add at least a 15U lockable cabinet
- 140 Crimp end drops
- 220 punch down drops

ECHS

- Underground fiber from main building to lunchroom
- Underground pipe in place from main building to Ag shop – Underground fiber ran from Ag Shop to Home Economics
- Underground fiber ran from lunchroom to Old Gym
- Underground fiber ran to gym in existing pipe
- Underground fiber ran to J Building in existing pipe
- Underground fiber ran to band room in existing pipe
- Underground fiber ran to Library in existing pipe
- Add 10U lockable cabinet in lunchroom
- Replace cabinet in Home Ec with 10U lockable cabinet
- Replace cabinet in Ag Shop with 10U lockable cabinet
- Replace cabinet in Library with 10U lockable cabinet
- Add an IDF in Room 100 with at least a 15U lockable cabinet
- 130 crimp end drops
- 190 Punch down drops