



Mobile County PUBLIC SCHOOLS

1 Magnum Pass | Mobile, Alabama 36618 | 251-221-4000 | www.mcpss.com

BOARD OF SCHOOL COMMISSIONERS
Sherry Dillihay-McDade, President - District 4
Don Stringfellow, Vice President - District 2
L. Douglas Harwell, Jr. - District 1
Reginald A. Crenshaw, Ph.D. - District 3
Johnny Hatcher - District 5

SUPERINTENDENT Chresal D. Threadgill

Purchasing Department
Phone (251)221-4473
Fax (251)221-4472
purchasing.mcpss.com

Bid No.: 23-49
Buyer: JULIE MORGAN

August 11, 2023

ADDENDUM #1
INVITATION TO BID
CUSTOM FABRICATED TABLES & SINKS
VARIOUS SCHOOLS

Please incorporate the changes to the bid specifications as discussed at the mandatory pre-bid meeting for Baker High School, bid item #7, as listed on page 2 of this Addendum.

If you should have any questions, please contact the Purchasing Department.

Sincerely,

Russell Hudson
Director of Purchasing

RH/jdm

Addendum #1

BAKER HIGH SCHOOL

ITEM 7 - 3-Compartment Sink with Drainboards-Baker High School – Qty 2

3-Comp sink with (2) 24" drainboards 120" long x 33 1/2" wide. All metals should be 300 series stainless steel with no galvanized metals accepted. Counter-top to be 14 gauge. Underbracing to be all welded stainless steel hat channel with sound deadening between metals. Tops to have marine edge at fronts and ends. 10" splash at rear with fully welded corners. (3) sinks to be 30" front to back x 24" left to right x depth 14" on right two sinks, depth 18" on left sink. Drains creased to center for proper drainage. corners coved in sink. Sinks fitted with twist lever drains. Fabricator to accommodate for (2) T&S Brass Faucet Model # B-0133-16-B08EL (provided by KEC) centered over sinks (model to be prerinse spray with faucet add-on 10" spout). Tubular legs to be 16 gauge stainless steel, fully welded. 16 ga Undershelf below drain board but no undershelf below sinks. Legs mounted to stainless steel gussets and fitted with adjustable bullet feet. Unit must be NSF approved and labeled.

KEC to fully install and plumb 3-comp sink, install drains onsite and provide faucets (verify faucet model number with MCPSS CNP Maintenance).