



# Wayne County Schools

Dr. Ricky Inman, Director of Schools  
Mrs. Charity Horton, Chairperson

419 South Main Street  
PO Box 658  
Waynesboro, TN 38485  
Phone: (931) 722-3548  
Fax: (931) 722-7579  
[www.waynetn.net](http://www.waynetn.net)

## **Bid Notice** **Wayne County High School Stadium Renovations** **Bids Due Thursday, February 6, 2025 at 2:00 P.M.**

Wayne County Schools is accepting bids for Stadium Renovations at the Wayne County High School (WCHS) Football Stadium. Bids must be submitted in a sealed envelope labeled "WCHS Football Stadium Renovation Bids" by 2:00 P.M., Thursday, February 6, 2025. No late bids will be accepted. Bids will be opened on the due date and presented to the Wayne County Board of Education at its regular meeting on February 13, 2025, at 5:30 P.M.

The project will include

- Preparing current structures as necessary and furnishing all materials and support, such as excavation, concrete, rebar, forming materials, and surface grout, to complete the following concrete repair/replacement on the home side bleachers.
- Replacement of railings and fencing.
- Construction of a new pressbox, including demolition of the existing structure.

The cost of the press box is requested to be included separately. All work must be completed by August 1, 2025.

Additional specifications and bid forms are available at [www.waynetn.net](http://www.waynetn.net) and the Wayne County Schools Central office at the above address. For questions about site visits, contact Ricky Inman at (931)722-3548 or [ricky.inman@waynetn.net](mailto:ricky.inman@waynetn.net).

The Wayne County Board of Education reserves the right to reject all bids.

# Wayne County High School Stadium

Construction and renovation of the home side stadium and Press Box:

707 S. Main Street, Waynesboro:

- 1) Remove the existing fence surrounding the home side bleachers and press box approx. 180ft
- 2) Replace the existing fence surrounding the home side bleachers and press box approx. 180ft.
- 3) Remove the existing railing from the front side of the walkway and down both ramps. Approx. 194ft.
- 4) Replace the existing railing on the front side of the walkway and down both ramps. Approx.194ft
- 5) New handrail to be powder coated (Black). Approx. 194ft
- 6) Prep and paint all exposed metal along bleacher fronts and sides (Black).
- 7) Resurface all existing concrete on bleacher seating and walkways with an approved material.
- 8) The contractor shall supply a set of stamped drawings for the foundation supports from an engineer that shows the existing structure and the new expanded press box.
- 9) The existing press box is 6x36. A new expanded press box to be 8x36 with an upper level added to be 8x36.
- 10) Aluminum composite panel system to be used for exterior cladding (color to be determined by owner). Must be a 20-year warranty on cladding.
- 11) Remove and haul away all debris.

## Explanation

- 1) Fence to be chain link black coated installed on existing post. Existing post to be painted black.
- 2) Railing along the front walkway to be 2"x 2"x 3/16" square tubing for guard rail, 42" in height and powder coated black.
- 3) 2"x 2"x 3/16" square tubing used for post and powder coated black.
- 4) 2"x 2"x 3/16" square tubing used for mid-rail and powder coated black.
- 5) Press box to be expanded by 2ft to the front, and a whole new upstairs to match the footprint of the lower level. 8'x36'
- 6) Windows to be 60"x 48" Black Aluminum clear Tempered glass Awning Fold Up Outswing type.

## WCHS Stadium Renovations Bid Sheet

Company Name: \_\_\_\_\_

Contact Person: \_\_\_\_\_

Phone Number: \_\_\_\_\_

Email Address: \_\_\_\_\_

Bid Amounts:

- Stadium repairs: \_\_\_\_\_  
(concrete, rails, fencing, etc.)
  
- Pressbox: \_\_\_\_\_