

P.O. Box 665 – 117 West Main Street
Hahira, GA 31632

Phone: 229-585-9018

E-mail:

mail@altmanbarrettarchitects.com



Letter of Transmittal

TO: Plan Holders

FROM: Keith Barrett

DATE: December 24, 2024

SUBJECT: Addendum 2
High School Addition To
Echols K-8 School
For
Echols County Schools

WE ARE SENDING YOU:

- Enclosed
- Prints
- Change order

- 2 Pages via EMAIL (including cover)**
- Specifications

ENCLOSED:


<u>COPIES</u>	<u>DATE</u>	<u>DESCRIPTION</u>
1	12/24/2024	Addendum 2

Transmitted as checked below:

- For your use**
- As requested
- For your information
- For review & comment
- No exceptions taken
- Exceptions noted
- Resubmit

REMARKS:

COPY : A+B File 23030 / A-1



ECHOLS COUNTY SCHOOLS

**HIGH SCHOOL ADDITION TO
ECHOLS K-8 SCHOOL
For
Echols County Schools**

**ADDENDUM NO. 2
December 24, 2024**

REVISIONS TO ADDENDUM 1:

- 1) In footer change "Addendum No. 2" to "Addendum No. 1".

REVISIONS TO THE SPECIFICATIONS:

- 2) Section 099120 Painting: 3.07 Paint Schedule Add "I Interior Concrete Floors: Provide the following painted finish over new interior concrete floors where a high performance coating is required:
 1. Semi Gloss Epoxy Finish: 3 finish coats of semi gloss epoxy floor coating.
 - a. First Coat:
PPG: Amerlock 2 VOC Epoxy Floor Coating
SW: Macropoxy 646 Fast Cure Epoxy (B58W00610)
 - b. Second Coat:
PPG: Amerlock 2 VOC Epoxy Floor Coating
SW: Macropoxy 646 Fast Cure Epoxy (B58W00610)

REVISIONS TO THE DRAWINGS:

- 3) Sheet D2100:
 - a) At Space 268 Principal's Office change "RB2" To" RB1" and "LV4" to" LV1".
 - b) At space 274 Vestibule change "LV4" to" LV1".
 - c) At space 240 Plant Science change "Sealed Concrete" to"Semi Gloss Epoxy".
 - d) Sealed Concrete see Spec 033000 Part 2 2.6 Liquid Floor treatments.
- 4) Sheet D2200:
 - a) At Space 224 Ag Lab change "Sealed Concrete" to "Semi Gloss Epoxy".
 - b) At Space 225 Supplies change "Sealed Concrete" to "Semi Gloss Epoxy".
 - c) At space 226 Equipment change "Sealed Concrete" to "Semi Gloss Epoxy".
 - d) Sealed Concrete see Spec 033000 Part 2 2.6 Liquid Floor treatments.

END