

Holtville School System Fence BID 23-013

1. Provide and install approximately 1730 linear feet of 6' tall black vinyl coated galvanized fencing with barb/twists above the top rail, and all accessories required. (See attached aerial image)
1. Provide 3 sliding gates (approximately 25 feet) with operator and keypad control equal to American Access DKE across the roadways. (See attached aerial images)
2. Provide a 4-foot-wide hinged gate with hardware and panic bars, and closer at each 25-foot gate.
3. Provide a 4-foot-wide hinged gate with hardware and panic bar, and closer across the sidewalk at the Holtville Elementary School dumpsters.
4. Provide approximately 110 linear feet of 6-foot wrought iron fencing and 22-foot double gate across the drive between the Highschool and Elementary school. Provide an approximately 4-foot wide hinged wrought iron gate across the sidewalk in front of the Elementary school.
5. Remove existing concrete bollards and yellow metal pole gate at the crosswalk between the high school and middle school.
6. Provide any and all clearing, grubbing, grading and debris removal for installation.
7. Provide concrete footing for fence posts.